





ILIMA Status Report

Helmut Weick, GSI
Darmstadt, 1st March 2011


- ❖ **FAIR Organization**
- ❖ **Working Groups**
- ❖ **New CR68**
- ❖ **TDRs**



FAIR GmbH Structure



NUSTAR/FAIR Project Management




Working Groups


ILIMA Working Groups / Technical Board

Sub-Project	Group Leader		Institute
Project Manager, Chair	H	Weick	GSI, Darmstadt
Simulation and Beam Handling	H	Weick	GSI, Darmstadt
Evaluation Software	Yu	Litvinov	GSI, Darmstadt
Physics and Theory Programs	Z	Patyk	Soltan Inst + Univ. Warsaw
ToF Detectors	W	Plaß	GSI + Univ. Giessen
Schottky Detectors	C	Kozhuharov	GSI, Darmstadt
Other Detectors	I	Dillmann	Univ. Giessen
<i>Spokesperson</i>	P	Walker	Uni. Surrey
<i>Deputy-spokesperson</i>	Yu	Litvinov	GSI, Darmstadt

Rings Overview




CR68: new layout with increased circumference



CR68: new isochronous mode


lower and higher γ_t ,



$$\gamma_t = \gamma = 1.84 \quad (E = 782.5 \text{ MeV/u})$$


$$\gamma_t = \gamma = 1.67 \quad (E = 624.1 \text{ MeV/u})$$

$$\gamma_t = \gamma = 1.43 \quad (E = 400.5 \text{ MeV/u})$$



Sergey Litvinov

CR68: different isochronous modes



γ_t		1.43	1.67	1.84
Q_x		2.28	2.15	1.93
Q_y		4.62	3.19	3.29
$\Delta p/p$	%	± 0.2	± 0.4	± 0.6
ϵ_x, ϵ_y	mm mrad	100	100	100
$ k_{quads.}^{max} $	[T/m]	4.02	2.58	2.96
$ k_{scx.}^{max} $	[T/m ²]	1.6	1.0	0.6

works also in new injection scheme with 2 kickers

Sergey Litvinov



WG: Simulation, Beam Handling


CR: Further ideas to improve isochronicity for larger emittance

- **Achromatic condition is essential, for isochronicity with respect to the transverse momentum spread (phase space).**
- **In ESR not even fulfilled to first order.
In CR possible up to second order with hexapoles.**
- **Power supply stability (short and long term)
 $\Delta I/I > \Delta m/m$, but only a bit ?**

WG: Schottky
see talk by Fritz Nolden

EC decay in ESR

cooling, 2 EC and 2 β^+ -decays





ToF Detector

- Faster DAQ, already now we can get spills at 2 Hz frequency.
Last beamtime unfortunately ToF detector failure,
but new LeCroy oscilloscope was tested with fast storage
~300 MB/s for new 7 or 20 GHz scope
- Test analysis with second ToF detector.
Possible in CSRe at Lanzhou ?
Do tracking and velocity measurement in non-isochronous ESR.
- Detector improvements see talk by Ronja Knöbel



WG: Particle Detectors

Get more experience with particle counting in addition to Schottky for lifetime measurements. Experiment E073 on alpha-decay, when?

Larger interest for more particle detectors in ring.

- (p, γ) , (α, γ) reaction experiment
- experiment on ^{19}Ne alpha decay of Phil Woods
- EXL new detector pockets → mounting before April 2011

One goal is detector on inside of dipole, charge pickup, β^- decay for ions with $Z < 50$.

DSSDs counters as well as MWPCs + scintillators.

FAIR Time Schedule

Roadmap

- Start of construction activities 2010/11
- Schedule is driven by civil construction
- Aim for earliest commissioning of accelerators and respective experiments

Module	Construction time (months)	Ready for installation
0	72	2015 / 16
1	28	2015 / 16
2	60	2016
3	60	2016


B. Sharkov

“The actual digging will start in 2012 after cutting the trees in 2011/2012.”

Time Plans

FAIR GmbH asks for time plans

More serious than before
TDR ? NESR ?



Name	Responsible	its	2010				2011				2012				2013				2014				2015				2016				2017				2018			
			Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4				
ELISE	H. Simon		NESR																																			
EXL	P. Egelhof		NESR	R&D and feasibility studies				step by step completion of the ESR set-up to a 10% version of the EXL recoil detector												TDR ready, produce roadmap for further procedure until 2020																		
		ESR	sign of a prototype setup at the ESR				feasibility studies and first experiments with radioactive beams at the ESR																															
ILIMA	H. Weick		CR	R&D				Eng. design				Construction				Installation and comm.																						
		NESR					R&D								Eng. design				Construction				Installation and comm.															
HISPEC/DESPEC	Gerl / M. Gorska		LEB	R&D		Prototyping				Contracting		Construction				Test		Installation and comm.																				
		FRS-S4	PRESPEC experiments at FRS-S4 employing HISPEC/DESPEC components as soon as available																																			
LASPEC	Ch. Geppert		LEB	R&D				Eng. design		Construction				Installation		Comm.																						
MATS	F. Herfurth		LEB	R&D				Eng. Design		Construction				Installation		Comm.																						
R3B	R. Lemmon		HEB Cave-C																																			

Similar plan for accelerators but backward from 2016



Status TDR Schottky

TDR includes: only res. Schottky in CR
mixer, cables
text of NIM article submitted

Open points: position in CR

People: Fritz Nolden, Shahab Sanjari,
Peter Hülsmann, Yuri Litvinov

Timeline: 2011

A Fast and Sensitive Resonant Schottky Pick-up for
Heavy Ion Storage Rings

F. Nolden^{a,*}, P. Hülsmann^a, Yu. A. Litvinov^{a,b}, P. Moritz^a, C. Peschke^a,
P. Petri^a, M. S. Sanjari^{a,c}, M. Steck^a, H. Weick^a, J. X. Wu^d, Y. D. Zang^d,
S. H. Zhang^d, T. C. Zhao^d

^a*Gesellschaft für Schwerionenforschung, Darmstadt, Germany*

^b*Max-Planck-Institut für Kernphysik, Heidelberg, Germany*

^c*Goethe-Universität, Frankfurt am Main, Germany*

^d*Institute of Modern Physics, Lanzhou, China*



Status TDR ToF-Detector

TDR includes: detector with HV electrodes, MCP, anode and cables
magnet
vacuum system
DAQ / oscilloscope

Open points: foil/MCP size – acceptance of CR
stray field shielding from quadrupoles
mounting in CR
analysis with two detectors
position resolution (no ?)

People: Wolfgang Plaß, Natalia Kuzminchuk,
Marcel (master student),
Helmut, Analysis working group
FAIR storage ring group at GSI

Timeline $\frac{1}{4}$ year until writing can start, if open points are solved

ILIMA Cost Table

only investments are counted, 2005 prices

	costs	no.	costs			costs	no.	costs
TOF detector					Storage ring development			0
new vacuum chamber for detector position	60	1	60					
vacuum chamber for pos2, parts reused	20	1	20					
magnets	5	2	10		Schottky			
vacuum pumps, valves controllers	90	1	90		Pick-ups CR	25	4	100
detector, MCP	25	2	50		Pick-ups NESR	25	8	200
Electronics, power supplies	25	2	50		Cavity couplings	10	12	120
slow control of HV and step motor	2	2	4		Cavity closings, incl. control	15	12	180
scaffolding with adjustment	2	2	4		Low-noise, broad-band amplifiers	25	12	300
cables for signals and control	2	1	2		DAQ			
DAQ					Amplifiers	1	12	12
DAQ(Oscilloscopes)	60	2	120		Remotely controlled tunable mixer	10	12	120
data storage	15	1	15		Remotely controlled tunable LO	10	12	120
			425 k€		Data acquisition, VME crate	10	2	20
Decay detectors					ADCs	1	72	72
vacuum pockets	20	4	80		Cables, connectors, and such	5	2	10
detectors with individual readout	54	2	108		data storage	15	1	15
DAQ								1269 k€
DAQ(VME crate + controller)	20	1	20					
			208 k€				sum:	1902 k€

As approved by CORE and as in our IMoU.
But for experiments only 78 M€ in total in start version.
Nustar cost book 54.5 M€ -> 22 M€ in start version.